PALACE MARAMATH DEPARTMENT, MYSORE.

Notification dated 17th November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Palace Engineer, Palace Maramath Division, up to 10th December 1930, for constructing Jackey's Quarters at Race Camp, Mysore. An approximate estimate of quantities and cost is given below. These quantities are not guaranteed. The work should be completed by the end of 15th March 1931.

2. The plans, detailed estimate and conditions may be seen at the Palace Engineer's Office at New Palace Offices between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Palace Engineer.

(*a*) The tenderer need only mention the percentage either higher or lower at which he is willing to undertake the work.

(*b*) He must be prepared to make use of materials available in the Maramath stores and Timber Yard, the cost thereof being recovered from his bills.

4. Each tender must be accompanied by a deposit of Rupees 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing two Cottages for Jackey's in Race Camp, Mysore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Huzur Secretary who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Palace Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Items not provided for in the estimate will be calculated as per schedule rates or as per data worked out during the execution of the work, subject to the same deduction of percentage as is agreed to by the contractor in his tender.

10. In matters of all disputes about rates, measurements, quantity and quality of works, etc., and in all other disputes of any kind, the decision of the Palace Engineer will be final and legally binding. Those who do not wish to abide by this condition need not tender.

Abstract estimate of the probable cost of constructing Jackey's Quarters at Race Camp, Mysore.

Sl. No.	Details of work	Quantity	Per	Rate	Amount
				Rs. a. p.	Rs.
1	Earthwork excavating foundations and filling in basement.	95	C.yd.	0 5 0	30
2	Chunam concrete foundations ...	1,436	C.ft	0 3 6	314
3	Brick in mud foundation and basement ...	1,934	,,	0 3 6	423
4	Basement slab 4", 2 lines dressed and fixed.	318	S.ft.	0 10 0	199
5	Brick in mud superstructure ...	4,626	C.ft.	0 3 9	1,084
6	Teakwood doors with panelled and glazed shutters (ply wood to be used for panels).	489	S.ft.	1 8 0	734
7	Teakwood glazed windows with bars ..	210	,,	1 12 0	367
8	Teakwood wall almirahs with shutters and 3 shelf planks (ply wood for panels).	90	,,	1 14 0	169
9	Teakwood wall cup boards with 2 shelves without shutters.	60	,,	0 12 0	45
10	Lintle slabs 4" undressed	261	,,	0 7 0	114
11	Teakwood front verandah pillars 7'x4½"x4½".	40	Each	8 0 0	320
12	Teakwood wrought and put up ...	62·20	C.ft.	5 12 0	357
13	Nandi wood work	173·96	,,	3 8 0	609

Sl. No.	Details of work	Quantity	Per	Rate	Amount
				Rs. a. p.	Rs.
14	Roofing with 1st class Mangalore tiles over Nandi rafters.	41·28	Sqr.	27 0 0	1,115
15	Flooring with Red Clay tiles over concrete bed and cement pointing.	22·16	„	30 0 0	665
16	Flooring with Cudapah slabs over concrete bed and cement pointing.	198	„	30 0 0	59
17	Chunam plastering—Rooms interior ...	84·48	„	3 8 0	296
18	Rustic plastering	11·40	„	5 0 0	57
19	Ridging with Mangalore tiles ...	217	R.ft.	0 8 0	109
20	Providing valley sheets	264	S.ft.	0 6 0	99
21	Teakwood eaves 12″ with beadings ...	283	R.ft.	1 0 0	283
22	Teakwood turned ornamental finals ..	4	Each	12 0 0	48
23	Do Pendants	20	„	1 12 0	35
24	Providing Sunshades over big size windows.	2	„	60 0 0	120
25	Providing mortar bands, etc., round doors and windows.	...	...	L. S.	50
26	Filling front gable with masonry and ornamental mortar bands, etc.	...	....	L. S.	30
27	Masonry U shaped drain 9″. ..	150	R.ft.	0 12 0	113
28	White washing 2 coats	84·48	Sqr.	0 4 0	21
29	Varnishing 2 coats. Doors and windows.	3·71	„	4 0 0	15
30	Zinc white painting 2 coats	8·59	„	4 8 0	39
31	Silicate painting 2 coats	48·49	„	4 0 0	194
32	Teakwood ornamental railings ...	63	R.ft.	2 8 0	158
33	Providing was hand basins complete sets.	5	Each	60 0 0	300
34	Giving water connection	...	...	L. S.	125
35	Electric Lights	...	..	L. S.	300
36	Forming roads, etc.	...	...	L. S.	25
37	Sundry unforeseen items	...	...	L. S.	100
	Total ...	...	...	...	9,121
	Add contingencies at 5 per cent ...	...	...	...	454
	Total ...	...	...	...	9,575
	Grand Total for two Quarters ...	...	...	...	19,150

H. C. BAPAT,
Palace Engineer.

MYSORE RAILWAYS, HASSAN.

Abstract Notification, dated 14th November 1930.

Attention of the intending contractors is hereby invited to the notice calling for tenders for providing convenience for Traffic and Engineering Staff at Hosahalli Station on Tarikere-Narasimharajapura Tramway, published in pages 1435 and 1436 of the *Mysore Gazette*, dated 13th November 1930.

Tenders will be received any working day up to 2 P.M. on 1st December 1930.

M. RAMAIYA,
Executive Engineer.